BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

Modified Schedule - B

NAME OF WORK: Providing Rain water harvesting facilities in ward no; 14 Bagalagunte T.Dasarahalli Sub Division

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the Engineer in charge of the work	Cum	32.25	130.00	Rupees One Hundred Thirty Only
E1RL1 2	KSRB 2-1.2 Eath work in surface excavation in hard soil for levelling and lowering the ground manually other than the foundation of buildings,culverts,road drains and trenches of pipe lines and cables and removing the excavated stuff to a distance not exceeding 50 mtrs and lift up to 105 mtrs excavated surface levelled after breaking of clods and neatly dressed disposed earth to be levelled after breaking of clods and neatly dressed as per specifications No KBS 2.1 (A) /2.3.1 P-5, I 2.2 PWD SR 2018-19	Cum	47.25	244.84	Rupees Two Hundred Forty Four and Eighty Four Paise Only
E1RL2 3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (KPWD SR 2018-19, Page No.13, Item No.4.2)	Cum	23.63	5615.66	Rupees Five Thousand Six Hundred Fifteen and Sixty Six Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
E1RL3 4	KRSB 4-1.5; Providing and laying in position plain cement concrete of mix M20 with OPC Cement @ 300 kgs with 20 mm and down size graded granite metal course aggregate @0.64 cum and fine aggregate @ 0.43 cum with super plastisicer @ 3 ltr conforming to IS 9103 -1999 Reaffirmed -52008 machine mixed concrete laid in layers not exceeding 15 cms thick well compacted in foundation and plinth and cills including cost of all materials,labour,HOM of machinary, curing etc complete as per specifications No;KBS 4.1,4.2 (P-12 ,I-.4.5 PWD SR 2018-19)	Cum	21.17	6167.66	Rupees Six Thousand One Hundred Sixty Seven and Sixty Six Paise Only
E1RL4 5	Providing and fixing granite benches including cost of materials labours as per specifications (Data Rate Approved)	Nos	42.00	11076.45	Rupees Eleven Thousand Seventy Six and Forty Five Paise Only
E1RL5 6	KSRB 4-6.4Providing and removing centering and shuttering strutting propping etc and removel of form work for vertical surface such as walls at any thickness including attached plasters ,buttresses plinth,cills and string courses including cost of materials labours as per specifications specification No;KBS 4.6.2 P-16, I-4.31 PWD SR 2018-19	Sqm	95.76	398.42	Rupees Three Hundred Ninety Eight and Forty Two Paise Only
E1RL6 7	Providing 20 mm thick cement plaster in single coat with cement morter 1;4 to stone masonry and concrete surface including rounding off corners wherever required smooth rendering and removing scaffolding including cost ofmaterials labour curing complete as per specifications	Sqm	204.96	301.59	Rupees Three Hundred One and Fifty Nine Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division